Articles.	Probable quantity required for the year.	Articles.	Probable quantity required for the year.
Indigo seeds free from dirt and stones per maund of 25 lbs.	600 lbs.	*Best bullock shined and tanned hide free from holes	10leathers
Wheat flour (best) do	250 lbs.	Do common do	5 do
Charcoal (best in bags), rate per bag	150 bags.	Large sheep skins do	10 do
Hemp thread per dozen ball	100 balls.	Boiled linseed oil, per bottle of 2½ seers.	50 bottles.
Cocoanut fibre best, Calicut, per maund of 25 lbs.	10,000lbs.	Turpentine oil do	30 do
Firewood (split in small strips)	1,200 lbs.	Copal varnish do	10 do
*Lac (Pegu) or Rangoon (free from sticks)	700 lbs	Black Japan do	10 do
*Red wood (split in small strips)	200 lbs.	Best French polish do	50 do
Chalk (white)	20 lbs.	Treacle do	10 do
*Best Indigo, 1st, 2nd and 3rd sorts	150 lbs.	Camphor (dry) per lb.	20 lbs.
Best tar	6 barrels.	Printing black ink per lb. tin	50 tins.
Wood oil	3 mds.	*White mule twist cotton No 10, per bale of 400 lbs.	5,000 lbs.
Yellow ochre or gopi	200 lbs.	* Do No. 20 per pack of 10 lbs.	100 lbs.
Pure cocoanut-oil	56 lbs.	*White cotton No. 30 do 5 lbs	50 lbs.
Pure gingelly-oil	50 lbs.	* Do No. 40 do	20 lbs.
Pure lamp-oil	75 lbs.	*Red cotton No. 40 do	40 lbs.
Best white rattan, 1st sort	350 lbs	*Yellow cotton No. 40 do	20 lbs.
Printing red ink, per lb. tin	20 tins.	*Green cotton No. 40 do	200 lbs.
Thick book binding calico, per yard	150 yds.	Sheet iron per maund of 25 lbs.	200 lbs.
Bleached broad thick malmal	30 do	Zinc do do	200 lbs.
Broad thick Turkey red cloth	30 do	*Bed ticking cloths per yard	30 yds.
One ft. broad tent gunny for bags per yard.	100 do	*2nd Sort white clipped wool, Mandya per maund of 25 yards	1,500 lbs.
Navy canvass No. I do	30 do	*2nd Sort black do Chitaldrug	1,000 lbs.
Do No. II do	5 do	*Fawn wool do do	2,500 lbs.
Do No. III do	5 do	*Chunam or scraped black	5,000 lbs.
*Bar iron per maund of 25 lbs.	200 lbs.	Do white wool	3,000 lbs.
Hoop iron do	200 lbs.	* Do fawn wool	1,000 lbs.
Files each	50 files.	Do grey wool	3,000 lbs.
Old brass per maund of 25 lbs.	200 lbs.	The wool is subject to be cleaned, picked, beaten out and washed before use.	
*1st Sort White clipped wool, Mandya do	500 lbs.	Timber teak, honne, black and rosewood in logs per cubic foot of various dimensions.	
*1st Sort Black clipped wool, Chitaldrug, do	1,500 lbs.	All other sundry articles besides these should be supplied by the Contractor regularly at the market rate.	
*Pundi fibre (white) do	800 lbs.		
*Best Buffalo hide free from holes	10leathers		

D. A. CHOKSI, *Superintendent.*

HASSAN DIVISION. [ADVERTISEMENT.

The 17th December 1895.

Tenders are hereby invited for erecting Rolled steel Girder bridges on Saklespur-Arehalli road.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's office, between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the Contractor, and forwarded in sealed covers to the Executive Engineer before the 6th January 1896. The work should be completed by the end of June 1897.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 750 as earnest money.

6. Within eight days of the acceptance of the tender, the Contractor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the Contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate of quantities and items of work required is given below. These quantities are not guaranteed.

10. Girders will be supplied.

Items.	Per.	Basavanhalli Bridge.	Kudrahalla Bridge.	Byadnihalla Bridge.	Total.
Concrete in surki mortar	C. ft.	1,424	1,752	1,499	4,675
Stone in surki mortar	,,	6,850	8,591	7,901	23,342
Pointing in chunam	Sqrs.	11·45	16·93	12·51	40·89
Stone slabs .. .	C. ft.	23	34	23	80
Diverting stream and baling water.. ..		(Lump sum Rs.)			
Excavation	C. yds.	432	661	436	1,529
Steel girders	Cwt.	68¼	136½	68¼	273
Iron works		Lump sum Rs.			
Carriage from Bombay		Lump sum Rs.			
Do tools and plant		Lump sum Rs.			
Fitting girders		Lump sum Rs.			
Teakwood work	C. ft.	274	521	274	1,069
Painting iron works		Lump sum Rs.			
Tarring wood work		Lump sum Rs.			
Rough stone wings	C. yds.	112	40	112	264
Date stone		Lump sum Rs.			
Approach Roads.					
Excavation	C. yds.	2,900	..	..	2,900
Earthwork	C. yds.	17,186	2,813	4,952	24,951
Turfing	Sqrs.	475·20	144·90	115·20	735·30
Gravelling	C. yds.	812	267	375	1,454
Compensation		Lump sum Rs.			
Cutting jungle		Lump sum Rs.			

A. S. NAGAVKAR, *Ex. Engineer.*

SHIMOGA DIVISION.

The 17th December 1895. [ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th January 1896, for re-constructing the remaining Barr Lines at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1897.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for re-constructing the remaining Barr Lines at Shimoga" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.